

City of Greenville, Ohio

MEMORIAL DRIVE WATER MAIN REPLACEMENT PROJECT

ADDENDUM #1 – March 11, 2019

BIDS RECEIVED MARCH 14, 2019 AT 2:00 P.M.

#1 Change “2” Gate Valve” to a “2” Curb Stop and Curb Box”

Revised Proposal Form:

Change the connection of the 2” and 8” water mains at Memorial and Locust. Changed is the “2” gate valve” to a “2” curb stop and curb box” in the bid form (Ref. No. 29).

Pg. 4 of Plans:

In the “Estimated Quantities” table, the Description of Reference Item #29 is changed from “2” GATE VALVE W/ 6” VALVE BOX” to read “2” CURB STOP AND CURB BOX”. The unit of measure of “EACH” and quantity of “1” are unchanged.

Pg. 9 and 11 of Plans:

The connection of the proposed 8” and 2” mains at the intersection of Memorial Drive and Locust Street is revised. The 8”x6” Tee, 6”x4” Reducer and 2” Gate Valve are to be replaced with an 8”x2” Tapping Saddle and 2” Corporation Stop. The cost of the saddle and corporation stop are to be incidental to the water main work.

Pg. 9 and 11 of Plans:

A 2” Curb Stop and Box is added to the plans, on the 2” main along Locust Street. The curb stop is to be installed in the grass, with a standard curb box. Any cost for seeding and mulching, due to curb stop installation, is to be paid under the “Seeding and Mulching, As Per Plan” bid item.

#2 Additional Changes at Water Superintendent’s Request

Pg. 4 of the Plans:

In the estimated quantities table,

The quantity of Reference No. 12, *Item No. 609 - “CURB REPLACED (IN-KIND)”* is changed from 10 FT. to 15 FT.

The quantity of Reference No. 20, *Item No. 638 - “3/4” WATER SERVICE BRANCH, AS PER PLAN”* is changed from 132 FT. to 156 FT.

The quantity of Reference No. 21, *Item No. 638 - “3/4” WATER SERVICE BRANCH, HORIZONTALLY DIRECTIONALLY DRILLED, AS PER PLAN”* is changed from 658 FT. to 563 FT.

Reference No. 24A, Item No. 638 - "5/8" METER, SETTING, STOP AND CHAMBER" is added, with a quantity of ONE (1) EACH.

Pg. 9 of the Plans:

The service branch to the home at 209 Memorial Drive is revised. The service was originally to be directionally drilled around the southwest side of the house, and connected to the existing service in the back of the home. The service is now to be open cut, and stubbed to the Right of Way line in front of the home, as shown in the revised plans. A meter pit shall be installed near the Right of Way line.

1. **2019-03-08_DARGRE1709_ADDENDUM1_11X17.pdf** (4.19 MB) in Production

<https://choiceoneengineering.filetransfers.net/downloadPublic/y5rrzqerv8j7cg4>

2. **2019-03-08_DARGRE1709_ADDENDUM1_24X36.pdf** (4.8 MB) in Production

<https://choiceoneengineering.filetransfers.net/downloadPublic/1xpbskfmquiq4wk>

These links will expire on **03/22/19 at 11:45 am EDT**

#3 – Revised Bid Form

A revised bid form is attached.

#4 – Current Plan Holders Listing

A current Plan Holders listing is attached.

END OF ADDENDUM #1